


CLIC two-beam module development

Status and future plans

G. Riddone



Outlook

- Short introduction
- CLIC Module
- Validation program
- Future steps



Main LINAC → two-beam modules

Main Beam Generation Complex



Energy	500 GeV A	500 GeV B	1.5 TeV	3 TeV
No. of sectors	10	8	24	48
No. of modules	4232	3726	10726	21452

CLIC Modules (boundary conditions,
technical system design and integration)

CDR modules

Prototypes

Laboratory


CLEX

Stringent technical requirements:


- Accelerating structure iris shape tolerance:
 - 5 μm
 - Active pre-alignment: $\pm 10 \mu\text{m}$ @ 1σ
 - Vacuum: 10^{-9} mbar
- Power dissipation: ~ 7.7 kW/module

In addition:


- Compact design to optimize the filling form
- Technology to lower the overall cost




Standard Module
73 %



Module Type 3
9 %



Module Type 2
12 %



Module Type 4
3 %

Standard Module (L = 2010 mm)

DB (100 A)

4 PETS, 2 Quads with BPM

Each PETS feeds 2 AS

MB (1 A)

8 acc. structures


MB filling factor: 91%

CLIC Module Type1


3 %



1 pair of AS replaced
by MB Quadrupole



+ special modules (damping region, modules with instrumentation and/or vacuum equipment) to be studied in TDR phase



Energy	500 GeV A	500 GeV B	1.5 TeV	3 TeV
No. of AS	26950	23826	71536	143072
No. of PETS	13475	11913	35768	71536

2010-2016

- **LAB version**




- **4 modules, 2 sequences foreseen**
 - **Type 1, Type 0, Type 0, Type 4**
 - **Type 0, Type 1, Type 0, Type 4**

Demonstration of the two-beam module design (from single technical system to complete modules)

This implies the assembly and integration of all components and technical systems, such as RF, magnet, vacuum, alignment and stabilization, in the very compact 2-m long two-beam module


- **CLEX version**



- **3 modules**
 - **Type 0, Type 0, Type 1**

Demonstration of the two-beam acceleration with beam and RF with real modules

Address other feasibility issues in an integrated approach




1) Currently under assembly and installation

2) Main components under procurement

- Essential learning process, so far:
- Fabrication procedure of the different technical systems
 - Assembly procedures (e.g acc. structure)
 - Integration of systems (few improvements already injected for next modules)
 - Girders (different design and material) and actuator behavior


3) Last module



Prototype module fabrication: RF system



Disk stack alignment
→ few tens of μm



8 Accelerating Structures



RF network



PETS








Girder: deformation under load $\leq 10 \mu\text{m}$ according to specification




Actuators: rangeability, backlash, hysteresis, resolution measured \rightarrow meet specification (From $\pm 1 \text{ mm}$ to $\pm 3 \text{ mm}$, $\leq 1 \mu\text{m}$, $\leq 0.5 \mu\text{m}$, $\leq 1 \mu\text{m}$)



Alignment bench with sensors

Supporting and positioning system (DB)

Supporting and positioning system (MB)




Vacuum Tank




Vacuum Manifolds



Extremity supports



DB-Quadrupoles



DB-Quadrupole (with BPM assembled)

- **First prototype Type 0 - Lab:**

- First 2-m accelerating structure stack completed
- RF network installation completed
- Under final leak test
- During assembly, validation of girders and supporting system → several alignment/positioning tests successfully performed

- **Next main steps:**

- **Thermo-mechanical tests together with alignment verification and vibration measurements**
- **Transport test and alignment verification**

- **First prototype Type 0 - CLEX**

- First double length from CIEMAT fully assembled
- Integrated supporting system (including girder, positioning system and Rf structure supports) under fabrication (ZTS-Boostec)
- Accelerating structures under machining at VDL





STEP 0 – Alignment tests

ENVIRONMENT

$T_{amb} = 20 \text{ \& } 40 \text{ } ^\circ\text{C}$

MEASUREMENTS

- a. Comparison between laser tracker and WPS measurements (no movements of girders)
- b. Alignment tests by moving girders via actuators and comparison between laser tracker and WPS measurements

STEP 1 – Heating environment

ENVIRONMENT

$T_{amb} = 20 - 40 \text{ } ^\circ\text{C}$

in steady-state conditions and by steps of 5 °C

HEATING

No active heating in RF structures

COOLING

No active cooling in RF structures

MEASUREMENTS

1. Temperature
2. Alignment
 - Laser tracker
 - Romer arm
 - WPS
 - Micro-Triangulation system

STEP 2 – Heating only PETS

ENVIRONMENT

$T_{amb} = 20 \text{ } ^\circ\text{C}$

in steady-state conditions

HEATING

PETS

by steps up to 110 W/unit

COOLING

PETS

< max calculated T

MEASUREMENTS

1. Temperature
2. Volumetric flow rate
3. Alignment
 - Laser tracker
 - Romer arm
 - WPS
 - Micro-Triangulation system

STEP 3 – Heating only AS

ENVIRONMENT

$T_{amb} = 20 \text{ } ^\circ\text{C}$

in steady-state conditions

HEATING

AS

by steps up to 400 W/unit

COOLING

AS

< max calculated T

MEASUREMENTS

1. Temperature
2. Volumetric flow rate
3. Alignment
 - Laser tracker
 - Romer arm
 - WPS
 - Micro-Triangulation system

STEP 4 – Heating all module

ENVIRONMENT

$T_{amb} = 20 - 40 \text{ } ^\circ\text{C}$

in steady-state conditions and by steps of 5 °C

HEATING

AS + PETS + DBQ

by steps up to max power/unit

COOLING

AS + PETS + DBQ


< max calculated T

MEASUREMENTS

1. Temperature
2. Volumetric flow rate
3. Alignment
 - Laser tracker
 - Romer arm
 - WPS
 - Micro-Triangulation system


Updated 7-Dec-2011 Alexandre Samokhine @ ceri.ch

Module Type 0 cooling scheme



- Nominal volumetric flow rate: 0.36 m³/h
- Water inlet temperature: 25 °C
- Water outlet temperature: 45 °C
- Power dissipation: 7.7 kW

Distribution of heat flux over 2 AS




Resulting temperatures inside the modules

Temperature [°C]	Prototype type 0
Max temp. of module	43
Water output temp. MB	35
Water output temp. DB	30



Resulting displacements on the DB and MB lines due to thermal, vacuum and gravity loads

Displacements [μm] (location and load type)	Prototype type 0
MB (RF load)	183
DB (RF load)	47
MB (vacuum load)	30
DB (vacuum load)	131
MB (gravity load)	27
DB (gravity load)	40


Deformed shape of prototype module type 0 due to applied thermal RF loads (values in μm)



*(2 AS = 820 W, PETS unit = 78 W, $T_{amb} = 25\text{ }^{\circ}\text{C}$
8 AS mechanical connected as one rigid unit)*



2013




3D model of integration of the first CLIC Module in CLEX (2013)

1 module T0

TBTS PETS tank


2014 - 2016





3 modules



in Beam line





- Design and integration of the two-beam module completed for CDR : compact design taking into account several stringent technical requirements but no cost optimization yet
- Program to validate design and main technical choices defined up to 2016:
 - 4 modules for thermo-mechanical tests in laboratory:
 - First module assembly completed
 - 3 fully fledged modules for tests in CLEX
 - First module installation during shut-down 2013-2014
- From assembly and testing of the first module
 - Supporting/alignment/positioning system according to the specifications
 - A lot of experience gained in the assembly of the RF structures, as well as on bonding and brazing processes
 - Few technical alternatives are already considered for the following ones: mini-pumps directly connected to RF structures
- Next steps:
 - Module system integration and cost optimization in collaboration with industrial companies (e.g RF structures, new technology and/or more compact design towards multi-featured disks)
 - Follow re-baselining evolution: one-beam design for 500 GeV klystron based configuration

Acknowledgement to the module WG members and several CLIC collaborators

*A. Samochkine, D. Gudkov, N. Gazis and F. Rossi highly
contributed to the preparation of this talk*

The background of the slide is a detailed technical drawing of an industrial piping system. It shows a complex network of pipes, valves, and flanges, rendered in a light gray line-art style. The pipes are connected to various components, including what appear to be heat exchangers or storage tanks. The overall layout is dense and intricate, typical of a process flow diagram or a detailed engineering drawing.

EXTRA

Vivien Rude, EDMS 1158356


Specifications			Boostec		Micro-Contrôle	
			Vertical	Horizontal	Vertical	Horizontal
Limite	From +/- 1 mm to +/- 3 mm	Limite	+ / - 2 mm	+ / - 3 mm	+ / - 1 mm	+ / - 1 mm
Backlash	$\leq 1 \mu\text{m}$	Backlash	$[-1 \mu\text{m}, 1 \mu\text{m}]$	$[-2 \mu\text{m}, 2 \mu\text{m}]$ Backlash à partir de 500 microns de déplacement pour RLA003	$[-1 \mu\text{m}, 1 \mu\text{m}]$	$[-1 \mu\text{m}, 1 \mu\text{m}]$
		Répétabilité	limite à 2h30	40 cycles sans problème	50 cycles sans problème	50 cycles sans problème
		Linéarité (cas classique)	$\sigma=1$ micron	$\sigma=1$ micron pour RLA001 $\sigma=3$ microns pour RLA002 $\sigma=10$ microns pour RLA003	$\sigma=3$ microns	$\sigma=2$ microns
Hystérésis	$\leq 1 \mu\text{m}$	Hystérésis	$[-1 \mu\text{m}, 1 \mu\text{m}]$	$[-1 \mu\text{m}, 1 \mu\text{m}]$ Problème quelques fois pour RLA003	$[-1 \mu\text{m}, 1 \mu\text{m}]$	$[-1 \mu\text{m}, 1 \mu\text{m}]$
Résolution	$\leq 0.5 \mu\text{m}$	Résolution	$0.17647 \mu\text{m}$	$0.2 \mu\text{m}$	$<0.1 \mu\text{m}$	$<0.1 \mu\text{m}$



Alexandre.Samochine@cern.ch



Reference -precision thermometer for PT100 calibration



Prepared by M. Sosin

solid state relay




NI Compact DAQ (8 slots) + LabView software




7 x NI9217 (4xPT100)
> 28 temperature input channels




1 x NI9422 (8xDO) > up to 8 channels for PWM heaters control



PWM signal for controlling the heaters



heaters




1 DOF for each heating sub-system (AS, PETS and DBQ)

max. temp. limit: 50 °C




Hardware thermal interlock (2 for AS, 1 for each PETS and DBQ)

temperature sensors

All temperature sensors are currently stored in the lab



NAME	LAB CONFIGURATION	PARAMETERS		
		Heating	Cooling	Vacuum
TT1	TM0	✓	✓	✗
TT2	TM0 + TM0	✓	✓	✗
TT3	TM1 + TM0	✓	✓	✓





Measuring arm Romer Multi Gage

- With a length of 60 cm, this kind of portable CMM allows to measure fiducials by probing or by one point. According to Romer, the maximum permissible error is less than 18 μm .



Micro-Triangulation system

- The principle of Micro-Triangulation is to use the full potential of a theodolite by substituting a CCD camera instead of the eye of an operator.
- This method has clearly demonstrated its high precision capability on the 2 m long mock-up where a precision about 10 μm along each axis has been obtained in the determination of the illuminated fiducials locations.





Laser tracker Leica AT401

- According to simulation calculations, the expected accuracy of AT401 measurements on a girder and its components is about 5 μm rms (up to 40 °C).
- Fiducials are measured with respect to a fixed reference system.
- Measurements taken from different stations can be elaborated and combined together.
- The measuring device must be at the same temperature of the parts to be measured.




Fiducials dedicated to Micro-triangulation

The aluminium main part of this fiducial (made in CERN) is equipped with a breakthrough ceramic ball with a diameter of 8 mm, a removable drawer which contain a LED allows to illuminate the accurate ball.



S. Griffet et al.

Tunnel simulation: temperature profile



- 5 thermocouples for each section
 - Thermocouple type T ($\pm 0.5\text{ }^{\circ}\text{C}$)
- 15 thermocouples in total
- Continuous acquisition during tests



NI 9214
16-Channel Isothermal Thermocouple
Input Module


LAB ENVIRONMENT

- Air conditioning and ventilation system: **end of October**
 - Main work for HVAC installation should start W42
 - Some smaller work should be done before with limited impact for the lab (move the compressed air supply, remove the sink/ fridge and furniture, move some lighting fixtures)



HEATING SYSTEM

- Heaters: **DELIVERED**
- Transmitters: **DELIVERED**
- Control hardware: **DELIVERED**
- Thermocouples + DAQ card: **DELIVERED**
- Electric scheme (IL, SSR, etc.): **COMPLETED**



COOLING SYSTEM

- Water supply: **DELIVERED**
- Hydraulic parts (pipes, elbows, etc.): **DELIVERED**
- Control valves: **DELIVERED**
- Measuring devices (pressure transducer, flow rate transducer, etc.): **DELIVERED**
- PRV: **DELIVERED**
- Safety valves: **DELIVERED**
- Supporting frames (beams, ladders, etc.): **end of September**
- Electric scheme: **COMPLETED**

