



RF Measurements and Documentation for the Industrial Fabrication of SC Cavities.


Alexey Sulimov,
DESY (Hamburg), 28 May 2013

ECFA LC2013

European Linear Collider Workshop

27-31 May 2013





RF aspects of quality control for XFEL cavities

RF Measurements and Documentation for the Industrial Fabrication of SC Cavities

IPAC'11

European XFEL
Description and First Experience with the RF Measurement Procedure for the European XFEL SC Cavity production
 A. Sulimov*, W.-D. Moeller, G. Keps, D. Kostin, J.-H. Thie, A. Goessel, T. Buehner, D. Reschke, K. Twarowski, Deutsches Elektronen-Synchrotron, DESY, Notkestrasse 85, 22607 Hamburg, Germany.

Abstract
 Cavity production for the European XFEL was recently started with first modules already arriving. From this stage to the accelerating motion being ready for the first installation, many critical RF measurements are necessary. During the mechanical cavity fabrication the cavity half-cells, dumb-bells and end-groups are measured and sorted. The cavity spectrum and field profiles are measured and tested. The HOM (Higher Order Modes) couplers filter tuning, vertical cavity RF tests, cavity checks during the string assembly and final cavity performance measurements in the module as well as the fundamental mode and HOM RF spectra measurements complete the sequence. We present the procedure of the RF measurements and discuss the first results for the XFEL prototype modules with special attention for the cavity tuning.

Table 1: RF Measurements for XFEL cavities.

Step	Measurements
Fabrication	<ul style="list-style-type: none"> Requirements of half cells. Requirements of dumb-bells. Requirements of end groups. Fundamental mode spectrum.
Treatment	<ul style="list-style-type: none"> Field profiles. HOM coupler filters characteristics.
Cold RF Test	<ul style="list-style-type: none"> Fundamental mode spectrum. Q_{ext}, Q_{int}. Q_{ext} of cavity probe antenna.
Assembly	<ul style="list-style-type: none"> Fundamental mode spectrum. HOM coupler filters characteristics. Field profiles.
Test	<ul style="list-style-type: none"> Cable calibration. HOM spectrum. Q_{ext}, Q_{int}. Q_{ext} for main input coupler.

Summary
 Series production of more than 80 9-cell TESLA type cavities for the European XFEL project not only requires high quality operation during all stages, but also maximal decrease of duration for each of step. The new equipment such as HAZARDA and new Cavity Tuning Machine allow reduction of the processing duration for corresponding RF measurements up to 80%.


Deutsches Elektronen-Synchrotron
 Helmholtz Association of German Research Centers
 22607 Hamburg, Germany
 www.desy.de, www.xfel.de

IPAC'11 HELMHOLTZ ASSOCIATION

RF aspects of quality control for XFEL serial cavities.

Production sequence:


- Cavity parts fabrication,
- Cavity welding,
- Cavity tuning,
- Welding in helium tank (HT),
- Pressure test (PT),
- Cavity transport.




Cavity parts fabrication

Cavity parts fabrication:

- Shape control for half cells (HC), end groups (EG) and dumb-bells (DB);
- DBs asymmetry control;
- Calculation of optimal parts lengths;
- DBs sorting in cavity;
- Estimation of cavity length in helium tank.




Cavity Welding (Acceptance Level 1)



After cavity welding:

- Measure the pi-mode frequency and cavity length;
- Control the welding parameters (shrinkage and deformation);
- Calculated the cavity length in helium tank.



RF Control after equator welding

Marked: 34 Details: Cavity parts

Cavity	Frequency(Pi) [MHz]	Length [mm] according XFEL.014			MAX deviation		Shrinkage [mm]	Material
		After welding	After tuning (expected)	Deviation	Trimming [mm]	Asym. -1		
CAV00544	1298.223	1279.96	1283.40	0.00	0.07	0.07	0.442	T

RF Parts Control

Cavity: CAV00544 Produced by: Zanon Shrinkage [mm]: 0.442


		Frequency [MHz]	Length [mm]	Asym.-1	Trimming [mm]
...	EGS	T00480	1296.525	161.70	0.013
...	DB1	T01008_T01076	1294.901	116.47	-0.020
...	DB2	T01079_T01225	1294.716	116.57	0.04
...	DB3	T01185_T01223	1294.695	116.32	-0.039
...	DB4	T00622_T01045	1294.415	116.38	0.000
...	DB5	T00783_T00956	1294.198	116.51	-0.03
...	DB6	T00784_T01068	1294.156	116.55	-0.01
...	DB7	T00655_T01040	1294.145	116.41	0.07
...	DB8	T01005_T01099	1294.330	116.61	0.03
...	EGL	T00417	1296.248	198.90	0.075

Cavity after welding	Frequency	Length	Maximum
1298.223	1279.96	0.07	0.075
		Average	
		0.03	

Remark:




Print Close

Cavity Tuning




Values are controlled during cavity tuning:

- pi-mode frequency,
- field flatness (FF),
- cavity length,
- cavity cells eccentricity.




Welding in Helium Tank and Pressure Test (Acceptance Level 2)



Welding in helium tank, pressure test:

- Control of pi-mode frequency during the rings with bellow and HT welding;
- Checking of RF parameters (Fpi, FF) before and after HT and PT.



RF Control after Acceptance Level 3

Marked: 8 Details: Results from Protocols Print Quit

Cavity	Frequency (Pi) [MHz]			Transmission [dB]	Spectrum deviation [kHz]	Field flat. (in HT)	Length [mm]	Maximum eccentricity [mm]	Warning
	Deviation (in HT)	in HT (Y_F02)	with vac (Y_F03)						
CAV00543	0.037	1297.393	1297.680	124	2.5	0.97	1058.49	0.17	
CAV00544	0.042	1297.388	1297.680	126	2.5	0.96	1058.58	0.26	
CAV00545	0.055	1297.375	1297.681	126	5.0	0.94	1058.54	0.22	
CAV00546	0.028	1297.458	1297.738	126	1.9	0.97	1058.93	0.28	

Detail RF Data Control


Cavity: CAV00543 Produced by: Zanon

Source	Frequency(Pi) [MHz]	Field flatness	Frequency deviation [MHz]	Spectrum deviation [kHz]	Comments / Remarks
X_F02	1297.451	0.98	0.001		OPEN_10
X_F03	1297.397	0.99	0.033		FMS_10
Y_F01	1297.408	0.97	0.022		RB_10
Y_F02	1297.393	0.97	0.037	2.5	TANK_10
Y_F03	1297.680		-0.070		Final spectrum, for Pi-mode reference value must be (1297.75 +/- 0.1) MHz

Source	Length [mm]	Max ECC [mm]	Comments / Remarks
X_M02	1058.53	0.19	OPEN_10
X_M03	1058.51	0.17	FMS_10
Y_M01	1058.49	0.17	RB_10

Accept Print Close

Cavity Transport (Acceptance Level 3)




To estimate Field Flatness (FF) changes the two spectra have to be compared:



- Reference spectrum SP2 can be downloaded from XFEL DB (it's a spectrum with known value of FF^{ref})
- $N = 9$ – number of cavity cells, measured spectrum $SP1 = \{f_i\}$, $SP2 = \{F_i\}$, where $i = 1 \dots N$.
- Relative spectrum is calculated as:
 $RS = \{R_i\} = \{F_i/f_i - F_N/f_N\}$, where $i = 1 \dots N$.
- Linear Fit is calculated for relative spectrum:
 $L = \{L_i\} = \text{linear_fit}\{R_i\}$, $i = 1 \dots N$
- Mean squared error is calculated as:

$$mse = \frac{\sum_{i=1}^N (R_i - L_i)^2}{N}$$
- Mean spectrum frequency deviation is calculated as:

$$MSE [kHz] = \sqrt{mse} \times \frac{f_{\pi}^{op}}{f_{\pi}} = 1.3GHz$$



Conclusion



RF Control after equator welding

Cavity	Frequency [MHz]	Length [mm] After welding	Length [mm] according XFEL #14 After tuning (expected)	MAX deviation	Trimming [mm]	Asym. -1	Shrinkage [mm]	Material
CAV98544	1298.223	1273.96	1283.48	6.08	6.87	0.87	0.442	1

RF Parts Control

Cavity: CAV98544

Part	Frequency [MHz]	Length [mm]	Asym. -1	Trimming [mm]
EGS	T00490	1296.525	161.70	0.013
DB1	T01008, T01076	1294.901	116.47	-0.05
DB2	T01079, T01225	1294.716	116.57	0.04
DB3	T01185, T01223	1294.895	116.32	0.02
DB4	T00622, T01045	1294.415	116.38	0.05
DB5	T00783, T00956	1294.198	116.51	-0.03
DB6	T00784, T01068	1294.156	116.55	-0.01
DB7	T00655, T01040	1294.145	116.41	0.07
DB8	T01035, T01099	1294.320	116.61	0.03
EGL	T00417	1296.248	199.90	0.075

Shrinkage [mm]: 0.442

Maximum: 6.87, Average: 6.83

RF Control after Acceptance Level 3

Cavity	Deviation (in HT)	Frequency (P0) [MHz] in HT (Y_F02)	with vac (Y_F03)	Transmission (dB)	Spectrum deviation [MHz]	Field flat. (in HT)	Length [mm]	Maximum occertricity [mm]	Warning
CAV98543	0.837	1297.393	1297.688	124	2.5	0.97	1058.49	0.17	
CAV00544	0.042	1297.388	1297.680	126	2.5	0.96	1058.58	0.26	
CAV00545	0.055	1297.375	1297.681	126	5.0	0.94	1058.54	0.22	
CAV00546	0.028	1297.458	1297.738	126	1.9	0.97	1058.93	0.28	

We appreciate:

- company **E.Zanon** for possibility to present the data.
- **IPP DESY group** for supporting the EDMS and data transfer.
- **DESY Data Base Team** for organizing the automation of data analysis.

THANK YOU !

Thank you all for attention !