



CLIC Status

D. Schulte for the CLIC collaboration



Timeline



From Steinar

2012-16 Development Phase

Develop a Project Plan for a staged implementation in agreement with LHC findings; further technical developments with industry, performance studies for accelerator parts and systems, as well as for detectors.



2016-17 Decisions

On the basis of LHC data and Project Plans (for CLIC and other potential projects), take decisions about next project(s) at the Energy Frontier.

2017-22 Preparation Phase

Finalise implementation parameters, Prive Beam Facility and other system verifications, site authorisation and preparation for industrial procurement.

Prepare detailed Technical Proposals for the detector-systems.



2022-23 Construction Start

Ready for full construction and main tunnel excavation.

2023-2030 Construction Phase

Stage 1 construction of a 500 GeV CLIC, in parallel with detector construction. Preparation for implementation of further stages.



2030 Commissioning

From 2030, becoming ready for data-taking as the LHC programme reaches completion.



Conclusion of the Accelerator CDR Studies



Main linac gradient	_ _	Ongoing test close to or on target Uncertainty from beam loading being tested
Drive beam scheme	-	Generation tested, used to accelerate test beam a specifications, deceleration as expected
	-	Improvements on operation, reliability, losses, mo deceleration studies underway



Luminosity





re





- Damping ring like an ambitious light source, no show stopper
- Alignment system principle demonstrated
- Stabilisation system developed, benchmarked, better system in pipeline
- Simulations on or close to the target

Operation & Machine Protection	_	Start-up sequence and low energy operation defined Most critical failure studied and first reliability studies
Implementation	-	Consistent staged implementation scenario defined Schedules, cost and power developed and presented
	_	Site and CE studies documented



Achieved Gradient for CLIC







Klystron-based Test Stands for CLIC



NEXTEF at KEK



ASTA at SLAC?



XBox1 at CERN operational with SLAC klystron



XBox2 at CERN, industrial klystron should be ready this year





Beam Loading Test Facility







Length, m

Test stand in CTF3 dog-leg to test gradient

with beam loading

- Structure can be power with klystron
- Can send drive beam through structure

System is commissioned Conditioned structure to come in summer

CLIC Test Facility (CTF3)





Recent CTF3 Results



- Operation with 8 times combination now routine
- New feedbacks added to improve phase stability

Goal is to achieve

- $\varepsilon_x = \varepsilon_y \cong 150 \ \mu m$ also for factor 8, currently ϵ_x =550µm due to orbit error
- Charge stability $\sigma_0 \approx 10^{-3}$ for factor 8

- Deceleration increased from 30% to 35%
- Decelerator BPM prototype tested (stripline, LAPP)
- Good understanding of the optics

Goal is to reach 40% deceleration

More results and more details in Roberto's talk







Recent CTF3 Results



- Structure with wakemonitor installed in TBTS
- Resolution is very good

Feedforward to correct drive beam phase

Phase monitors successfully tested

Goal:

- Install kickers and amplifiers (FONT5) in summer
- First tests in autumn





CTF3 Team

D. Schulte, CLIC Status, May 2013

INFN Frascati JAI/Oxford

[...

CLIC Drive Beam Front End Hardware Prototypes and Plans



Preliminary Schedule

Task	2013	2014	2015	2016
	prepare gun test		testing with HV	
Gun test area	area	ready for first tests	modulator	testing
Gun	design	Prototype, first tests	gun tests	
SHB Buncher	fabrication	testing low power	testing high power	
500 MHz power source	specifications	purchase	needed for test	
1 GHz structure	specs, mech. design	construction	low power test	high power test
Diagnostis	design	design	tests in gun area ?	
LLRF	specs	fabrication+test	ready for klystron test	
1 GHz klystrons	tender, contract	Design review	Receive first prototype	Klystron 2
1 GHz Modulator	R&D	R&D	Receive first MDK	MDK2
1 GHz rf test stand	specs, location	prepare	Receive MDK, klystron	Ready for testing
	Measure CTF3,			
RF stability	DESY?	Measure SLAC ?		



CLIC Two-beam Module





Module program until 2016:

- 4 modules in the lab (thermo-mechanical validation), first one being successfully tested
- 3 modules in CLEX (tests with beam and RF), first under fabrication to be ready end of the year

G. Riddone, Module Team



Test-module Test







Module with existing PETS priming



SiC girder at Boostec (FR)

All safety measures implemented (power dissipation ~7 kW per module)

DAQ and control system (Labview based) tested and validated

First tests promising and in line with FEA simulations 12

Instrumentation Example: ODR Monitor 🐠 [·••



Setup (chemically etched target)



Silicon TARGET



Silicon Carbide MASK

Photographs by Lilian REMANDET



First molecular adhesion target results at CESR-TA

Vertical direction





Goals: **Beam lifetime** ... Single turn interference images

ODR (optical diffraction radiation)



D. Schulte, CLIC Status, May 2013





Stabilisation Progress



New sensor is being developed First promising results

Position verified to be 0.25nm





Prototypes for module under production Long magnet design



D. Schulte, CLIC Status, May 2013

ystèmes et matériaux pour la



Main Linac Alignment



5230







Beam Delivery Progress



Optimisation for lower energies is ongoing, reduction of beta-functions appears possible

ATF2 is an important test facility

• we contribute to the operation and to specific experiments -> see Rogelio Tomas on Tuesday

CLIC FFS design can be applied to ILC

Could use similar hardware, in particular hybrid final focus magnet could be interesting -> Michele Modena

R. Tomas et al.





Stabilisation Experiment





D. Schulte, CLIC Status, May 2013

CLIC Beam-Based Alignment tests at FACET

clc



Before correction

After 1 iteration

After 3 iterations

19

Ŀ.

Rebaselining: Goals for Next Phase



- Iterate on energy choices
 - Stage optimised for 375GeV for Higgs and top
 - 1-2TeV depending on physics findings, will still also do Higgs
 - 3TeV as current ultimate energy, includes more Higgs
- Focus on optimisation of first energy stage
 - But consider upgrades
- Identify, review and implement cost and power/energy saving options
 - Identify and carry out required R&D
- Re-optimise parameters (global design)
 - Develop an improved cost and power/energy consumption model
 - Iterations needed with saving options
- Study alternatives
 - E.g. first stage with klystrons
- Need to remain flexible, since we are waiting for LHC findings
 - But have some robustness of specific solutions and can anticipate this to some extent





Rebaselining Status



- Ingredients are
 - Automatic structure design
 - Automatic beam parameter and machine design
 - Automatic costing
- Automatic structure design
 - Old procedure is available
 - Improved version using better understanding of RF limitations is in preparation
- Automatic parameter choice and machine design
 - Improved modelling of damping ring, further limitations in preparation, in particular electron cloud and impedances
 - BDS with smaller beta-functions at lower energies being studied
 - Automatic injector design is in preparation
- Automatic costing
 - Cost from CDR used for main linac
 - More recent understanding for drive beam generation

CLIC Drive Beam Klystron Based on ILC Design









RF efficiencies (67.8%, 68.8%) validate feasibility of CLIC target at 1GHz (70%)



Voltage, kV

Voltage, kV



20 MW L-band Klystron for CLIC





Recommended parameters of the L-band klystron for CLIC

Parameter	
Frequency, GHz	1.0
N beams	6
Cathode diam., cm	4.94
Cathode loading A/cm ²	1.76-1.96
µ–perveance/beam	0.45
Peak power (max), MW	20-25
Cathode Voltage, kV	160 - 180
Cathode current, A	180-202
Efficiency, %	>70



20+MW at 1GHz corresponds to 10MW at 1.3GHz Cost derived by detailed study of components Call for tender in preparation



Modulator





Study integrated klystron+modulator system High phase stability requirement

Novel topologies are being studied

- at 400V and at O(18kV)
- simulations are promising
- validation of components and full prototypes planned

D. Schulte, CLIC Status, May 2013

ETHZ, LAVAL, U. Nottingham, CERN

> D. Aguglia et al.



Some Identified Savings



- Electron pre-damping ring can be removed with good electron injector
- Dimension drive beam accelerator building and infrastructure are for 3TeV, dimension to 1.5TeV results in large saving
- Possible drive beam accelerator klystron power has been underestimated
- Potential to use cheaper material for the drive beam accelerator structures
- Systematic optimisation of injector complex linacs in preparation
- Power consumption:
 - Has been calculated running overheads flat out
 - Obviously to conservative



Study of Klystron-based Alternative



Only interesting for first energy stage at 375GeV cms Would need ~30,000 klystrons at 3TeV

2-pack solid state

Simple parametric cost study has shown that nominal structure CLIC_G is very good for klystron-based approach Can use the same structure for drive beam and klystron-based option

<u> </u>	
Linac energy overhead	10%
Linac filling factor	≈ 0.75
Number of klystrons	4484
Number of structures	17936
Active length/single linac	2.242 km
Length/single linac:	3 km
bunches/pulse	312
particles/bunch	$3.72 \cdot 10^{9}$
repetition rate	50 Hz
Luminosity	$10^{34} \mathrm{cm}^{-2} \mathrm{s}^{-1}$





Study of Klystron-based Alternative II



Reduced klystron power compared to NLC/JLC

Fairly mature

Improved designs being made



RF in	1/4	TEO1 lir ↓ 1,	_{ле} т /з	ap-off e	extracto	or 1/1	Commo vacuum network	n	
							P		H

General				
structures per unit	8			
Unit length [m]	2.0			
Energy gain per unit [MeV]	183			
Klystron				
Pulse length [ns]	1950			
Peak power [MW]	59			
Voltage [kV]	460			
Current [A]	234			
Efficiency [%]	55			
Dual moded SLED II pulse compressor				
One delay line length [m]	17.7			
Output pulse length [ns]	244			
Output power [MW]	490			
Power gain	4.64			
CLIC_G accelerating structure				
Structure length [m]	0.23			
Input RF power [MW]	61.3			
Gradient (loaded) [MV/m]	100			

I. Syratchev et al.



Links to Other Applications



Undulator

~50 m



Linac-3

~5 GeV

Linac-2

2.5 GeV

~120 m

X band linac

Injector

-50 m

S band linac

D. Schulte, CLICE tatus, May 2013 the proposed X-Band LINAC and FEL facility

200 MeV

Gun

ntroduction	Stelliar STAFINES
Council Chamber, CERN	08:30 - 08:40
CLIC activities/plans	Walter WUENSCH 🗎
Council Chamber, CERN	08:40 - 08:55
'SI activities/plans	Dr. Ricardo ZENNARO 🗎
Council Chamber, CERN	08:55 - 09:10
rieste/Fermi plans	Dr. Gerardo D'AURIA 🗎
Council Chamber, CERN	09:10 - 09:25
ERA activities/plans	Ugo AMALDI 📄
Council Chamber, CERN	09:25 - 09:40
Shanghai activities/plans	Dr. Qiang GU et al. 📋
Council Chamber, CERN	09:40 - 09:55
singhua	Jiaru SHI 📄
Council Chamber, CERN	09:55 - 10:10
ALBA	Mr. Francis PéREZ 📄
Council Chamber, CERN	10:10 - 10:25
Coffee	
Council Chamber, CERN	10:25 - 10:45
SLAC activities/plans	Prof. Sami TANTAWI 📄
Council Chamber, CERN	10:45 - 11:00
Ankara/Turkish activities/plans	Avni AKSOY 📄
Council Chamber, CERN	11:00 - 11:15
//AX-lab	Mrs. Francesca CURBIS 📄
Council Chamber, CERN	11:15 - 11:30
Argonne activities/plans	Dr. Wei GAI 📋
Council Chamber, CERN	11:30 - 11:45
Short discussion	
Council Chamber, CERN	11:45 - 12:00

Example of Electron Linac RF Unit Layout





Future CLIC klystrons would save O(20%)

Power, norm.

Thanks to the Growing CLIC Collaboration



CLIC multi-lateral collaboration - 48 Institutes from 25 countries



ACAS (Australia) Aarhus University (Denmark) Ankara University (Turkey) Argonne National Laboratory (USA) Athens University (Greece) BINP (Russia) CERN CIEMAT (Spain) Cockcroft Institute (UK) ETH Zurich (Switzerland) FNAL (USA)

Gazi Universities (Turkey) Helsinki Institute of Physics (Finland) IAP (Russia) IAP NASU (Ukraine) **IHEP** (China) INFN / LNF (Italy) Instituto de Fisica Corpuscular (Spain) IRFU / Saclay (France) Jefferson Lab (USA) John Adams Institute/Oxford (UK) Joint Institute for Payer and Nicear CLIC Status, May 2013 (Spain) Research SOSNY /Minsk (Belarus)

John Adams Institute/RHUL (UK) JINR Karlsruhe University (Germany) KEK (Japan) LAL / Orsay (France) LAPP / ESIA (France) NIKHEF/Amsterdam (Netherland) NCP (Pakistan) North-West. Univ. Illinois (USA) Patras University (Greece)

PSI (Switzerland) RAL (UK) RRCAT / Indore (India) SLAC (USA) Sincrotrone Trieste/ELETTRA (Italy) Thrace University (Greece) Tsinghua University (China) University of Oslo (Norway) University of Vigo (Spain) Uppsala University (Sweden) UCSC SCIPP (USA)



Conclusion



- The CDR volumes document
 - The feasibility studies for CLIC
 - A staged approach to implement the project
- The work on the development phase is progressing
 - Rebaselining is on the way with focus also on low energy
 - The hardware development programme is being implemented
 - Focus on cost and industrialisation
- Collaborations are formed to promote the use of CLIC technology for other applications
- Thanks to the CLIC collaboration for the slides and work presented
- My excuses to those whose work I could not present this time and to those whose name did not appear explicitly