
ILC Status

After the Technical Design Phase

Presentation to SiD prepared by:

Marc Ross (SLAC)

October 14, 2013

Completing the TDP: Outline

- TDP Goals:
 - » R & D to enable Project Proposal and updated Value estimate – with Cost Containment
 - » Technology Transfer
 - development a strong industrial base
- Technical Design Report:
 - » Consists of two parts: 1) R & D Report and 2) Design Description
- Beam Test Facilities:
 - » SRF Linac: Fermilab NML, DESY E-XFEL and FLASH, KEK STF
 - » Beam Dynamics: Cornell CsrTA (2008 – 2010)
 - » Beam Tuning: KEK ATF2
- Production / Industrialization:
 - » CEBAF Upgrade and E-XFEL

Completing the TDP: Outline

- TDP Goals:
 - » R & D to enable Project Proposal and updated Value estimate – with Cost Containment
 - » Technology Transfer
 - development a strong industrial base
- Technical Design Report:
 - » Consists of two parts: 1) R & D Report and 2) Design Description
- Beam Test Facilities:
 - » SRF Linac: Fermilab NML, DESY E-XFEL and FLASH, KEK STF
 - » Beam Dynamics: Cornell CesrTA (2008 – 2010)
 - » Beam Tuning: KEK ATF2
- Production / Industrialization:
 - » CEBAF Upgrade and E-XFEL

Technology Transfer for ILC

- Asia (Japan and China)
 - » Japan: 'Col Stream': Construction started at KEK (~16 M\$) for cavity process / test / cryomodule assembly / test. Construction funded; Operations funds (~60M\$) to be allocated 10.2013
 - » Goal of Col Stream: applications of SRF using ILC technology. Many diverse applications listed.
 - » Hope: Col Stream facility will make KEK a 'hub-lab' capable of standard ILC cryomodule assembly and test
- EU
 - » EU – XFEL construction →
- US
 - » LCLS-II Project at SLAC →

Innovation 'Generation' Program (MEXT)



文部科学省

MINISTRY OF EDUCATION,
CULTURE, SPORTS,
SCIENCE AND TECHNOLOGY-JAPAN

文字サイズの変更

会見・報道・お知らせ

政策・審議会

白書・統計・出版物

申請・手続き

文部科学省の紹介

教育

[トップ](#) > [科学技術・学術](#) > [産学官連携、地域科学技術振興](#) > [革新的イノベーション創出プログラム \(COI STREAM\)](#)

● 革新的イノベーション創出プログラム (COI STREAM)



今の夢。10年後の常識。
新しい未来を作りたい。

文部科学省では、現在潜在している将来社会のニーズから導き出されるあるべき社会の姿、暮らしの在り方(以下、「ビジョン」という。)を見通した革新的な研究開発課題を特定した上で、既存分野・組織の壁を取り払い、企業だけでは実現できない革新的なイノベーションをイノベーション創出プログラム (COI STREAM)」を開始する予定です。

2012 supplementary budget, Industry-University cooperation COI program: Generation of 'Earth-Cleaner' market

地域資源等を活用した産学連携による 国際科学イノベーション拠点整備事業
地球を守るアース・クリーナー市場を創出する 新産学連携拠点

Status of COI program 10142013

COI : Center Of Innovation


KEK Aerial – Showing COI Stream Footprint



COI building : promotion of superconducting accelerator utilization


New building (80m x 30m) is under construction at North of STF

Superconducting Accelerator Development Hall (2014)



SC cavity inspection & process, vertical test, cryomodule assembly, cryomodule test⁸

Building location



超伝導加速器利用促進化推進棟周辺電気設備配線図

Cut and Flatten for new COI building

09132013

STF building





new COI building is now under final detail design,
Completion will be November 2014.




EU Highlights (mostly XFEL)

- Application to EU for ILC-bridging funds under [Horizon 2020](#) FP program
 - » Signs of 'interest'
- Intensive industrialization and production of 1.3 GHz ILC - style SRF technology
- Reported at 'SRF 2013', Paris 23-27.09.2013

European XFEL Large Grain Cavities (or LG advertisement for future projects)



Comparison of Q_0 at 2 K for 11 EP-treated LG cavities (red) with Q_0 at 2 K of XFEL prototype cavities (AC115–AC129, best result) treated according to XFEL recipe (blue).





E_{acc} performance of LG cavities in XFEL cryomodule XM-3.



The cryomodule has ca. 60% lower cryogenic losses in CW, compared to all 4 previously tested cryomodules (J. Sekutowicz).

For details see presentation of C. Madec THIOA02



E. Zanon: Status September 10th. Delivered 69 CAVs. More details in Talk THIOA01





RI: Status September 10th. Delivered 42 CAVs. More details in Talk THIOA01



EP facility, EB welding and 3D-measurement equipment (courtesy of E. Zanon)









Yield of gradients: After re-treatment (2. pass)

- Yield of usable and maximum gradient of 64 cavities (2.pass):
50 cavities passed in 1.pass + 14 cavities after re-treatment
- Average gradients increased + spread reduced (standard deviation)



Average maximum gradient:

(30.9 ± 4.4) MV/m

EZ: (30.4 ± 4.5) MV/m

RI: (32.3 ± 4.1) MV/m

Average usable gradient:

(29.0 ± 3.9) MV/m

EZ: (28.4 ± 4.0) MV/m

RI: (30.6 ± 3.1) MV/m



7 assembly area +1
=> 8 weeks of assembly



Ramp-up : XM1 to XM8 : 2 weeks per area
=> 16 weeks



Ramp-up from Sept. 2013 to Dec. 2013

Production : Dec. 2013 on



EU - XFEL

- Cavity production lines fully functioning: 8 cavities / week
 - » Two companies
- Coupler production quality improved
- Cryomodule production:
 - Three pre-series CM (XM-3, XM-2, XM-1) in process; typical time to construct 4 months; time to test unknown (XM-2 now in cool-down)
 - Production series of 81 each started Sep. 02, 2013; full rate from Dec 2013 (until Oct 2, 2015)
 - One CM / week; one production line (CEA-Saclay)
- 24 cavities to be used for high – gradient development

SLAC Proposal:

- Following BESAC (Basic Energy Sciences Advisory) report in late July:
 - » Shakeup of US accelerator construction projects:
 - » SLAC LCLS-II project redefined
 - » ANL APS upgrade program redefined

- SLAC Proposal:
 - » 4 GeV CW SRF Linac-based FEL
 - » Use ILC / XFEL 1.3 GHz technology
 - » Installed in the first 1/3 of the SLAC linac housing
 - » (50 year old S-band linac to be completely removed)
 - » **First light end of FY 2019**

SLAC Director Chi-Chang Kao, 27 September 2013:

SLAC

SLAC Today Story Archive

From the Director: A Modified Proposal for LCLS-II

September 27, 2013

by Chi-Chang Kao

A few weeks ago, I [wrote about a recent report](#) from the Subcommittee on Future X-ray Light Sources of the Basic Energy Sciences Advisory Committee (BESAC). The report strongly endorsed the science that can be facilitated by X-ray free electron lasers and called for a facility that could provide beams with both high per pulse energy and high repetition rate to allow for the exploration of revolutionary new science. As I wrote, we were asked by the Department of Energy's Office of Science to explore how we might incorporate the report's recommendations into our plans for the upgrade to the Linac Coherent Light Source (LCLS). We developed a modified plan on how we could accomplish this.

Today, I want to give you more details on this plan for meeting BESAC's recommendations. Let me first caution that what I'm explaining here is just a proposal. No decisions or funding commitments have been made. However, we are beginning to work more closely with the Office of Science and partner with other national laboratories to assess the feasibility, cost and schedule of this proposal, so I want to make sure all of you at SLAC are kept as up to date as possible.

To meet BESAC's recommendations, we have proposed constructing a 4 GeV superconducting linear accelerator in the first third of our existing linac tunnel. Rather than building a new undulator tunnel as was called for in the original design for LCLS-II, we now propose placing two variable-gap undulators in the existing undulator tunnel: a new soft X-ray undulator and a hard X-ray undulator that would replace the existing LCLS undulator. The existing LCLS instruments would be upgraded to take advantage of the new configuration. The undulators, when fed by the superconducting linac, would enable a new class of experiments making full use of the high repetition rate and lower intensity pulses, such as high resolution and multi-dimensional X-ray spectroscopy. It will still be possible to feed the new hard X-ray undulator with electrons from the existing linac to provide pulses with high energy, high intensity and very short duration. The new plan would allow us to incorporate all the capabilities called for in the BESAC subcommittee report and help the U.S. maintain its world leadership in light sources and LCLS to continue to set the standard for cutting-edge scientific discovery.



SLAC Lab Director Chi-Chang Kao. (Credit: Matt Beardsley)

Tags

[Department of Energy](#)

[Director's Columns](#)

[LCLS-II](#)

Share



[Print this article](#)

If the proposal is approved and funded, we will need the help of a number of partners to help make it a reality as soon as possible. We have begun discussions with other national laboratories that have expertise in areas such as superconducting radio frequency, high repetition rate injectors and undulators to explore how we may work together.

We have worked closely with the Office of Science on this proposal but as I said, there is a ways to go before any decisions are made with regard to whether we move forward with these modifications. We need to remain mindful that we continue to live in a very constrained funding environment. Until and unless our response to BESAC's recommendations moves beyond the proposal stage, it is too early to discuss timing or schedules for this modified plan. However, we strongly agree that the opportunities for exciting science laid out in the BESAC report with such an instrument are unprecedented.


RF Parameters:

RF Parameters (CW SRF Linac)	symbol	nom. value	units
RF frequency	f_{RF}	1.3	GHz
Average RF gradient (powered cavities only)	E_{acc}	16	MV/m
Installed 1.3 GHz voltage (all cavities)	V_{13}	4.6	GV
Fraction unpowered cavities	V_{off}	6%	-
Mean cavity quality factor (unloaded)	Q_0	2	10^{10}
Mean cavity quality factor (loaded)	Q_L	4	10^7
Cavity operating temperature	T_{cryo}	1.8	K
No. of 9-cell cavities per cryomodule (1.3 GHz)	N_{cav}	8	-
Cavities per power amplifier in L0 and L1	-	1	-
Cavities per power amplifier in L2 & L3	-	48	-
Total installed cryomodules (1.3 GHz)	N_{CM}	35	-
Total spare cryomodules (1.3 GHz)		1	-

RF Parameters (2)


RF power per cavity (average)	P_{cav}	6.3	kW
Total number of 3.9-GHz Cavities	-	12	-
Max. 3.9-GHz crest voltage	V_{39}	60	MV
No. installed CMs in L0	N_{CM0}	1	-
No. installed CMs in L1	N_{CM1}	2	-
No. installed 3-9-GHz CMs in linearizer	N_{CMLH}	3	-
No. installed CMs in L2	N_{CM2}	12	-
No. installed CMs in L3	N_{CM3}	20	-
SC Cryogenic AC Power	P_{Cryo_AC}	5.4	MW
RF AC Power	P_{RF_AC}	3.5	MW
<i>Estimated RMS Stability Goals:</i>			
RF phase stability (rms, pulse-to-pulse)	$(\Delta\phi_{RF})_{rms}$	0.01	deg
RF amplitude stability (rms, pulse-to-pulse)	$(\Delta V/V_{RF})_{rms}$	0.01	%

LCLS-II - Linac and Compressor Layout for 4 GeV



Linac	V (MV)	ϕ (deg)	Acc. Grad. (MV/m)	No. Cryo Mod's	No. Cav's	Spare Cav's	Cavities per Amplifier
L0	97	*	14.6	1	8	1	1
L1	235	-26	15.1	2	16	1	?
HL	-40	-170	-	3 (3.9GHz)	12	0	12?
L2	1448	-28	15.5	12	96	6	32?
L3	2460	0	15.7	20	160	10	32?

Includes 2-km RW wake



* L0 phases: (-40°, -52°, 0, 0, 0, 13°, 33°), with cav-2 at 20% of other L0 cav's.

First 800 m of SLAC linac (1964):



Much LCLS-II construction will be done at Fermilab, using infrastructure intended for ILC

18 CM? (50%)

Other CM to be made at JLab (and Cornell)

US team have made ~ two ILC CM. LCLS-II effort will help understand US-domestic technical, cost, and industrialization


ILC R & D initiative: Power Coupler development

Mandated by PAC (12.2012) technical review

Issues:

- Cost
- Copper coating / flaking
- Complex Assembly
- Plug-compatibility

Bringing power into the cryomodule – the coaxial power coupler:



SLAC expertise

September 6, 2013

Marc Ross, SLAC LCLS-II

Power Input Coupler WG

Agenda suggested by Wolf-Dietrich

1. Specification

- General specification N. Solyak
- Power capacity C. Adolphsen
- Thermal balance D. Kostin
- Tune-ability &nb sp; H. Hayano,
(maybe the max power and the tune-ability could be one talk)

2. RF and technical design and cost

- EU/AM W.-D. Moeller
- JP &nbs p; E. Kako
- Assembly TBD
from KEK, DESY
- Interfaces/integration/compatibility
H. Hayano
- Comparison, pros & cons TBD, discussion
- Cost aspects A. Yamamoto

3. Fabrication

- Critical fabrication steps (cu-plating, brazing vs welding...)
Companies

4. Discussion for the ILC oriented coupler design


Some open questions/comments:

- Should we talk about cost ?
- **We would like to have coupler experts not involved in the TTF3 or KEK design, e.g. from CERN** or other labs, who?


Discussed at CERN and the following persons
advised by L. Evans

- Eric Montesinos (RF Coupler Expert)
- Jose Miguel Jimenez (Vaccum Group L.)
- Leonel Marques Antunes Ferreira (Cu plating)

Comparison of Input Couplers



- TTF-III
- Two bellows
 - 40 mm D.
 - 125 kW
- KEK-STF-II/QB
- Single bellows
 - 60 mm D
 - (40 mmD to be tried)
 - 350 kW



ATF2 Program Status

Glen White, SLAC

January 2013

Detector measures
signal **Modulation Depth "M"**


$$M = \frac{N_+ - N_-}{N_+ + N_-} = \left| \cos(\theta) \exp(-2(k_y \sigma_y)^2) \right|$$

$$\Rightarrow \sigma_y = \frac{d}{2\pi} \sqrt{2 \ln \left(\frac{|\cos(\theta)|}{M} \right)}$$



measurable range
determined by **fringe pitch**

$$d = \frac{\pi}{k_y} = \frac{\lambda}{2 \sin(\theta/2)}$$



depend on
crossing angle θ (and λ)



Laser Interfere Fringe



N: no. of Compton photons
Convolution between e- beam profile and fringe intensity



Crossing angle θ	174°	30°	8°	2°
Fringe pitch $d = \frac{\pi}{k_y} = \frac{\lambda}{2\sin(\theta/2)}$	266 nm	1.03 μm	3.81 μm	15.2 μm
Lower limit	20 nm	80 nm	350 nm	1.2 μm
Upper limit	110 nm	400 nm	1.4 μm	6 μm

Expected Performance


Measures

$\sigma_y^* = 20 \text{ nm} \sim \text{few } \mu\text{m}$
with < 10% resolution


$$\sigma_y = \frac{d}{2\pi} \sqrt{2 \ln \left(\frac{|\cos(\theta)|}{M} \right)}$$

σ_y and M
for each θ mode


select appropriate mode
according to beam focusing





174 deg.



30 deg.



2 - 8 deg



Crossing angle
continuously
adjustable by
prism

Vertical table

1.7 (H) x 1.6 (V) m

- Interferometer
- Phase control (piezo stage)

path for each θ mode
(auto-stages + mirror actuators)

13/05/29

Role of IPBSM in Beam Tuning


beforehand
Construct & confirm laser paths, timing alignment

precise position alignment by remote control

transverse : **laser wire scan**

Longitudinal: **z scan**

MeV/ICT




laser spot size
 $\sigma_{t,laser} = 15 - 20 \mu\text{m}$



Zscan

crossing angle 174


Date: 2013 03 14
Time: 23:08:04



Fringe Scan 30 degrees



Coup2 Scan 121220_144102



Modulation	0.635	+/-	0.028
Beam Size	128.8	+/-	6.8 nm
Average	1033.502	+/-	24.206
Phase	4.498	+/-	0.056

After all preparations

continuously measure σ_y using fringe scans

→ **Feed back to multi-knob tuning**


Beam time status in 2012

Spring run

Feb; 30 deg mode commissioned
(1st M detection on 2/17)

stable measurements of $M \sim 0.55$

- 2 - 8 ° mode: clear contrast ($M_{\text{meas}} \sim 0.9$)
- Prepared 174 deg mode commissioning



Major optics reform of 2012 summer

By IPBSM group@KEK

- Suppress systematic errors
- Higher laser path stability / reliability

Winter run

- High M measured at 30 ° mode
- Contribute with **stable operation** to ATF2 beam focusing / tuning study

12/20 :
1st success in M detection
at 174 deg mode

$10 \times \beta_x^*$, $1 \times \beta_y^*$

preliminary

Last 2 days in Dec run

Measured many times $M = 0.15 - 0.25$
(correspond to $\sigma_y \sim 70 - 82$ nm)

* IPBSM systematic errors uncorrected

** under low e beam intensity ($\sim 1E9$ e / bunch)

Large step towards achieving ATF2 's goal !!
error studies ongoing aimed at deriving "true beamsize"

Beam time status in 2013 Spring

Stable IPBSM performance → major role in beam tuning

measured M over continuous reiteration of linear /nonlinear@ tuning knobs @ 174° mode


dedicated data for error studies under analysis

174° mode "consistency scan"

2013/03/14

after IP-BSM roll alignment
after IP-BSM pitch alignment

$M \sim 0.306 \pm 0.043$ (RMS)
correspond to $\sigma \sim 65$ nm




moving towards goal of $\sigma = 37$ nm :

higher IPBSM precision and stability

& looser current limits of normal / skew sextupoles current

Fringe scan crossing angle (degree) 174

Date: 2013 03 08
Time: 22:27:15




Fit results: $A \cdot \sqrt{1.0 + M^2} \cdot \cos(x + Ph)$

Modulation: 0.385 ± 0.025

Beam Size: 58.4 ± 2.0 nm
-1.9

measure M vs time
after all conditions optimized

Modulation 174 deg



ILC Project: Mysteries of the Universe

Outreach event in Tokyo,
tomorrow, 10.15

宇宙の謎に迫れるか!
国際リニアコライダー計画
ILC計画・国際シンポジウム

入場無料
(定員300名)
事前申込が必要です。

2012年7月に「ヒッグス粒子発見!？」というビッグニュースが世界を駆け巡りました。各国の研究者たちはヒッグス粒子を超える未知の素粒子や新たな物理現象を探すための新型加速器「国際リニアコライダー (ILC) 計画」を推進しています。世界が注目するILC計画が日本を有力建設候補地として本格的に動き始めた今、国内外の科学者と専門家をお招きし、ILC計画によってもたらされる日本の新たな「科学技術立国」の道をテーマに国際シンポジウムを開催いたします。

2013年10月15日(火)
開場・受付 15:00 開会 15:30
会場: 東京大学伊藤国際学術研究センター
東京都文京区本郷7-3-1

基調講演

- 村山 斉 (東京大学 五次元物理学 宇宙物理学 教授)
- 山崎 直子 (宇宙飛行士)
- リン・エバンス (リニアコライダー国際グループ チェアマン)
- マイク・ハリソン (CERN-FLUKAヘビィイオン研究所)
- 内永 ゆか子 (NPO法人 J-ARC 代表)
- 池上 彰 (ジャーナリスト 東京大学名誉教授)
- 大宮 英明 (三菱重工 取締役会長 日本経済団体連合会 副会長)

【主催】リニアコライダー・コラボレーション (LCC) / 東京大学素粒子物理国際研究センター (ICEPP) / 先端超伝導科学技術推進協議会 (AAI)
【後援】 素エネルギー加速器研究機構 (KEK)

Report from the Science Council of Japan on ILC

Published September 30
(see comments from LCC
Directorate last week)
Available in Japanese

回 答

国際リニアコライダー計画に関する所見



平成25年（2013年）9月30日

日本学術会議

SCJ Report Charge (informal translation)

- About scientific significance of research at ILC project, position of ILC within particle physics
- About the position of ILC project in the whole scientific community
- About the impact of carrying out ILC in our country to nation and society
- About constraints - such as the required construction budget, governance of ILC, and securing human resources

SCJ Conclusions:

important issues that should be examined:

- (1) More clear explanation of ILC project particle physics , taking upgrade LHC into account.
- (2) Budget Framework that does not cause stagnation for action on national problems and progress of the field of arts and sciences
- (3) International cost sharing
- (4) The role of domestic teams led by the associated researchers such as High Energy Accelerator Research Organization (KEK) or universities
- (5) Human resources that are necessary for construction period and driving period, particularly lead management.

It is necessary for a clear prospect to be provided about these problems in judging the right or wrong of inviting ILC in our country.

KEK Internal Evaluation of ILC – including Cost-review

The ILC site selection and SCJ report publication have helped move the KEK Accelerator Laboratory to launch a series of meetings for discussion of related issues – including cost.

(this group is nominally tasked with Super KEK-B and JParc upgrades.)