


Tile characterization measurements in Heidelberg

Konrad Brigg
Kirchhoff-Institut für Physik
Ruprecht-Karls Universität Heidelberg



Outline



- Large Tile Testing System
- Characterization Measurements
- Future Plans



Reminder - Tile Testing System

Setup:

- 216 tiles can be inserted in a tile holder plate
- Readout electronics and fiber system (12 channels) inside Positioning head moved to 18 measurement stations
- Tiles lit by 375nm pico-second laser, pulse with $\approx 30\text{ps}$
- Laser intensity fixed, common HV



Measurement procedure

- Voltage scan of 15 Points, measured up to $\approx 3V$ over-voltage
- Dark rate spectrum (5kEvents) and Single photon spectrum (20kEvents) taken
- About 2 minutes per measurement (12 tiles in parallel)
- Full measurement of 216 tiles takes about 45 minutes





Characterization of 149 Uni HH Tiles

- 149 wrapped tiles measured in Heidelberg end of November
- Runs with 50ns and 100ns integration time
- Fiber calibration runs (5h)
- No repeated runs for error estimations
- 100ns runs show lower χ^2 in preliminary analysis, these results are shown here.
(6 tiles missing in this dataset)





SiPM quality

- Spectra show good peak separation from 0.7V above breakdown
- Noise levels about 20% higher compared to small system (Noise from Positioning Stage)
- Out of 149 tiles, 3 do not show any acceptable spectrum




Parameter extraction

- In order to improve fit results, some work on gain error estimation and spectrum quality cuts necessary
- Mean signal in expected bias region ≈ 10 px
- Measured Npx points fitted with a pol(2) function



SiPM breakdown voltage



- Distribution shows similar structure as seen in Hamburg measurements.



- Mean errors from fits: 100mV

Preliminary results!





SiPM breakdown Voltage

- 22 tiles have also been characterized by Uni Hamburg
- Differences: 300mVpp + Offset, RMS(Δ)~64mV




Tile signal response

- Light yield not corrected for fiber system non-uniformity here.
- Laser intensity not tuned to actual MIP response ($\approx 20\text{px/MIP}$ at this operating region)



Fiber system intercalibration

- Positioning head is moved in steps of 1x1 tiles.
- Most of the tiles are measured with each channel.
- Full measurement consists of ≈ 1500 individual measurements




Mean signal for each channel at constant over-voltage



Fired Pixels – Relative spread

Signal for each tile scaled by mean signal from fiber calibration runs



Relative Signal spread for detector operated at constant over-voltage


Allows crosscheck with other measurements and first estimation of measurement uncertainties.



Light yield equalisation

Reading of Uni Hamburg light yield characterization database not yet implemented

→ Absolute light yield per MIP not accessible.



Light yield equalization can be performed on the basis of a voltage operation point.

Mean pixel response is equalized around e.g. $\langle V_{ov} \rangle = 3V$

Estimation by solving the $N_{px}/N_{px,channel} = 1$ functions in Taylor expansion up to 2nd order



Summary and Outlook

- Large scale system successfully operated with a larger number of tiles
- Good spectrum quality, noise from positioning stage under control
- Significant differences in comparison with prior Uni Hamburg characterizations
- Careful analysis of systematics to be done, some system parameters will have to be tuned
- Tile response equalisation can be performed using a mean operating point.



- 300 tiles will be measured for the test-beam in January
- Repeated measurements to determine system stability and systematics planned



Backup



Detailed pictures of the system



Detailed pictures of the system

